This list is not a complete list or accurate total of all asbestos containing materials. Quantities derived from the use of this list will be estimates only. All contractors are responsible for quantifying materials based upon their own observations. It is the contractor's responsibility to quantify the asbestos containing materials and determine cost projections based upon their own independent quantifications. The bidding contractors are responsible for any costs or logistical problems incurred due to discrepancies found in this document. Envirotest is not responsible for budget overruns, costing errors, time delays, scheduling conflicts, and change orders derived from the use of this data.

Flooring: the Envirotest staff reviewed data from previous inspection reports, then inspected and/or tested the flooring in approximately 100 locations. This flooring list was compiled with from the data gathered during that process. Unfortunately, additional asbestos flooring materials will be found as carpet and multiple layers of surface flooring are removed from the building. Evidence of floor floating, pouring cement over original flooring, and installing divider walls and cabinetry on top of flooring were found. Therefore, this list will be incomplete and will need to be adjusted as carpet and other finish materials are removed which conceal original asbestos flooring materials. This list is not a complete and accurate total of asbestos flooring materials. Quantities derived from the use of this list will be an estimation only.

Asbestos Flooring Location Listing

Level 1	**Level 2**	**Level 3**
101	201 A&B	Cafeteria (Rear Half)
103	202	308
105	205	311
107	207	312
109	209	313
115 (Not in Scope)	210 A, B, C, D, E	314
116, A & B	211	316
118 A & B	212	317
120	213	319 & 319A
160	215	320
Mechanical Rooms	216 South	321
	217 & 217A	322
	218 South	323
	219 & 219A	326
	223	326A (328)
	Mechanical Room 2-M1	327
		329
		332
		Mechanical Rooms

Vent Hood Panel Locations
Room 308
Room 314
Room 316
Room 320
Room 322
(Cafeteria Vent Hoods are untested)

Mirrors Mastic Locations
All Restrooms
Stage Area (Auditorium)
Weight/Fitness Area (Gym)
Cosmetology (Not in Scope?)

HVAC Ductwork Mastic Locations
Room 221
Conservatory?
(Additional Areas Possible)

Pipe Run Insulation Locations
Room 118
Selective Pipe Chases
(Sampled in Pipe Chase from 164A to 309)
(Additional Areas Possible Include the Attic and Abandoned Basement)

Hard Elbow Pipe Fitting Locations
Found Near Exterior Walls of Rooms
Sampled in Rooms 102, 105, 226
(Additional Areas Certain)

Mastic on Pipe Fitting Locations
Found Throughout the Building
Sampled in the following locations:
Mechanical Room (1-M1)
Level 1 Hallway Near Room 101
Room 102
Room 105
Room 221
Room 226

Boiler Flue and Water Tank Insulation Location
Large Mechanical Room Near Gymnasium
Room #1-M1 on the Level 1 Floor Plan